

Agenda
Regular Work Session of the Mayor and Council
City of Chattahoochee Hills, Georgia
May 30, 2019/6:00 p.m.

Discussion Items

1. Council Meeting Agenda Review – Robbie Rokovitz
2. 2019 Road Improvements (TSLPOST) RFP update – Robbie Rokovitz
3. Rico Crossroads Community Zoning – Michael Morton

Mayor and Council Reports and Comments

2019 ROAD IMPROVEMENTS – PATCHING

Bid Date: Thursday, June 20, 2019, 11:00 a.m.

Project Specifications

Project Scope: The project consists of “deep patching” (mill & inlay) repair of various roads as outlined below. All milling quantities are based on the use of a 4’ wide milling head. All patching asphalt quantities are based on an average depth of 3.5” of asphalt binder. Precise locations have not been determined but will be marked in conjunction with Contractor prior to commencement of actual work. The tonnage shown for each road is an estimate and may be adjusted as required to match field conditions.

Location #1 – Rico Road: This section lies between South Fulton Parkway and Hutcheson Ferry Road and is 3.5 miles in length. The majority of project patching will be performed on this road section. The estimated quantity is 1850 tons.

Location #2 – Hutcheson Ferry Road: This work consists of minor deep patching in three primary portions of the road between Atlanta Newnan Road and Cochran Mill Road. The estimated quantity is 100 tons.

Location #3 – Cochran Mill Road: This work consists of minor deep patching of the road between Wilkerson Mill Road and Hutcheson Ferry Road. The estimated quantity is 150 tons. It is noted that this section of road is planned for future full depth reclamation due to existing condition. Based on low traffic volumes, the identified areas will be patched to help extend the life of those sections until further repairs can be programmed.

Location # 4 – Rivertown Road: This work consists of minor deep patching of the road between Campbellton-Redwine Road and Cochran Mill Road. The estimated quantity is 150 tons.

Location # 5 – Campbellton-Redwine Road: This work consists of minor deep patching of the road near the intersection with Rivertown Road. The estimated quantity is 25 tons.

Location # 6 – Atlanta Newnan Road: This work consists of minor deep patching of the road near the intersection with Rico Road. The estimated quantity is 25 tons.